

DIN EN 12889
Trenchless Construction and Testing of
Drains and Sewers

and

DWA-A 125E
Pipe Jacking and Related Techniques

Mai 2009, corrected version September 2020

DINE EN 12889
Grabenlose Verlegung und Prüfung von
Abwasserleitungen und -kanälen

DWA-A 125
Rohrvortrieb und verwandte Verfahren

PREVIEW

DIN

DIN EN 12889

**Trenchless Construction and Testing of
Drains and Sewers**

and

DWA-A 125E

Pipe Jacking and Related Techniques

Mai 2009, corrected version September 2020

DINE EN 12889

Grabenlose Verlegung und Prüfung von
Abwasserleitungen und -kanälen

DWA-A 125

Rohrvortrieb und verwandte Verfahren



Standard DWA-A 125 and DVGW Standard GW 304 (German version) are identical in content.



DIN EN 12889¹⁾

Trenchless construction and testing of
drains and sewers

January 2000



DWA-A 125E
Pipe Jacking and Related Techniques

December 2008

The German Association for Water, Wastewater and Waste (DWA) is strongly committed to the development of secure and sustainable water and waste management. As a politically and economically independent organisation it is professionally active in the field of water management, wastewater, waste and soil protection.

In Europe DWA is the association with the largest number of members within this field. Therefore it takes on a unique position in connection with professional competence regarding standardisation, professional training and information. The approximately 14,000 members represent specialists and executives from municipalities, universities, engineering offices, authorities and companies.

Imprint

Published and sold by:
DWA German Association for
Water, Wastewater and Waste
Theodor-Heuss-Allee 17
53773 Hennef, Germany
Tel.: +49 2242 872-333
Fax: +49 2242 872-100
E-Mail: info@dwa.de
Internet: www.dwa.de

Printing (English version):
DWA

ISBN:
978-3-942964-37-1 (Print)
978-3-96862-096-1 (E-Book)

Printed on 100 % recycled paper

© DWA, 2nd edition, corrected version as at September 2020, Hennef 2020.

All rights, in particular those of translation into other languages, are reserved. No part of this publication may be reproduced in any form – by photocopy, digitalisation or any other process – or transferred into a language usable in machines, in particular data processing machines, without the written approval of the publisher.

¹⁾ Reproduced by permission of DIN Deutsches Institut für Normung e. V. The definitive version for the implementation of this standard is the edition bearing the most recent date of issue, obtainable from Beuth Verlag GmbH, Burggrafenstraße 6, 10787 Berlin, Germany

Introduction to the Joint Publication

The European Standard EN 12889 "Trenchless Construction and Testing of Drains and Sewers" was developed within the scope of harmonising the European rules and standards with the aim of reducing trade barriers.

With the publication of DIN EN 12889 in March 2000, the standard was awarded the status of a German standard. Thus, it represents the state of technology for trenchless installation and testing of new drains and sewers with pre-fabricated pipes and their connections.

Standard DWA-A 125E "Pipe jacking and related techniques" deals with the underground installation of pre-fabricated pipes with different geometry of the cross-section. During the installation, a cavity is created in the ground by displacing, ramming, drilling, pressing or other installation. The pipes are either pulled, pushed or pressed into this cavity, or existing sewers or pipelines are passed and/or replaced.

DIN EN 12889 and Standard DWA-A 125E do not exclude each other and they do not regulate the same facts in different ways either.

For enhanced handling and legibility, this joint publication provides the reader with both texts – DIN EN 12889 and Standard DWA-A 125E – in a clearly structured way.

For enhanced legibility, the texts have been synoptically summarised in sections. The text taken from DIN EN 12889 is highlighted white. The supplementary information and recommendations contained in Standard DWA-A 125E succeed the text taken from DIN EN and are highlighted grey.

National Foreword (DIN EN 12889)

This European standard was elaborated by the Technical Committee TC 165 "Waste water engineering" (German office) of the European Committee for Standardization (CEN).

The work was conducted by the "Installation of buried pipes for gravity drain and sewer systems" working group (WG 10) of CEN/TC 165. Task force V 34 "Installation of buried pipes for gravity drain and sewer systems" (CEN/TC 165/WG 10/CEN/TC 164/TC 165/JWG 1) of the "Water supply" (NAW) was involved in the work for Germany.

EN 12889 "Trenchless Construction and Testing of Drains and Sewers; German version 12889: 2000" is the first European standard that deals with trenchless installation of drains and sewers as a supplement to the common open-cut method of construction according to EN 1610. Standard ATV-A 125E "Pipe driving", September 1986 edition (identical with DVGW Advisory Leaflet 304 "Pipe jacking"), which was elaborated by the joint ATV-DVWK working group 1.5.3 "Trenchless construction methods" and introduced in European committees by the AA V 34 "Installation of buried pipes for gravity drain and sewer systems" task force of NAW in cooperation with working group 1.5.3, provided the fundamental basis for elaborating this European standard, which has now been included as national standard DIN EN 12889 in the German DIN set of standards. However, it was not possible to consolidate the areas of water supply, wastewater discharge and gas supply in one European standard on "trenchless installation of pipelines" at the level of European standards as regulated by A 125/GW 304.

DIN EN 12889 and ATV-A 125E and/or DVGW GW 304 do not exclude each other and they do not regulate the same facts in different ways either. Yet, in many aspects, A 125E/GW 304 contains details that are not yet dealt with and covered by this first version of the European standard. Therefore, both technical regulations supplement each other.

Later revisions of A 125E/GW 304 and/or DIN EN 12889 reserve the right to amend technical contents or edit the text and to consider other European standards and further requirements.

Owing to the current situation and by taking the positive practical experience into account, which has been gained with A 125E/GW 304, it is essential to also consider ATV Standard A 125E and/or DVGW Advisory Leaflet GW 304 when working with DIN EN 12889.

Introduction

English version

Trenchless Construction and Testing of Drains and Sewers

Mise en oeuvre sans tranchée et essai des branchements et collecteurs d'assainissement

Grabenlose Verlegung und Prüfung von Abwasserleitungen und -kanälen

This European Standard was approved by CEN on 15 November 1999.

CEN members are bound to comply with the CEN/CENELEC Internal Regulations which stipulate the conditions for giving this European Standard the status of a national standard without any alteration. Up-to-date lists and bibliographical references concerning such national standards may be obtained on application to the Central Secretariat or to any CEN member.

This European Standard exists in three official versions (English, French, German). A version in any other language made by translation under the responsibility of a CEN member into its own language and notified to the Central Secretariat has the same status as the official versions.

CEN members are the national standards bodies of Austria, Belgium, Czech Republic, Denmark, Finland, France, Germany, Greece, Iceland, Ireland, Italy, Luxembourg, Netherlands, Norway, Portugal, Spain, Sweden, Switzerland and United Kingdom.

Foreword

This European Standard has been prepared by Technical Committee CEN/TC 165 "Waste water engineering", the secretariat of which is held by DIN.

This European Standard shall be given the status of a national standard, either by publication of an identical text or by endorsement, at the latest by July 2000, and conflicting national standards shall be withdrawn at the latest by July 2000.

According to the CEN/CENELEC Internal Regulations, the national standards organizations of the following countries are bound to implement this European Standard: Austria, Belgium, Czech Republic, Denmark, Finland, France, Germany, Greece, Iceland, Ireland, Italy, Luxembourg, Netherlands, Norway, Portugal, Spain, Sweden, Switzerland and the United Kingdom.

Annex A is informative.

Since the publication of the previous version of this Standard, there have been numerous technical developments. To a large extent, the structure of this Standard was adapted to DIN EN 12889 "Trenchless construction and testing of drains and sewers". On this note, Clause 6 takes additional techniques relating to pipe jacking into account.

Neither do this Standard and DIN EN 12889 exclude each other, nor do they regulate the same facts in different ways. However, this Standard contains details in many aspects that the European Standard does not yet deal with at this point.

Standards DVGW GW 304 and DWA-A 125 are identical. Technical developments may cause changes, especially in the numerical values given here. The state of the technology shall be taken into consideration.

The presented process engineering and empirical data were taken from current practice. The empirical data may be exceeded under unbeneficial circumstances.

In technically founded individual cases, it can be deviated from the regulations of the Standard – with the agreement of the institution responsible.

Note:

This publication contains DIN EN 12889 and Standard DWA-A 125E respectively in the original [English] text. The passages of text originating from Standard DWA-A 125E have a grey background.

Authors

The Standard has been elaborated by the DWA-Working Group ES-5.3 "Trenchless Methods of Construction" within the DWA-Sub-committee ES-5 "Construction".

The DWA-Working Group ES-5.3 "Trenchless Methods of Construction" has the following members:

BECKER, Wolfgang	Dipl.-Ing., Berlin
BLOSFELD, Jürgen	Dipl.-Ing., Bergisch Gladbach
BRUMUND, Oliver	Dipl.-Ing. (FH), Bad Soden-Salmuenster
BRUNE, Peter	Dipl.-Ing., Saarbruecken
BÜSCHEL, Klaus	Dipl.-Phys. Dipl.-Wirtsch.-Phys., Bonn
DIETEL, Eckhard	Dipl.-Ing., Uelzen
DOLLOWSKI, Peter	Dipl.-Ing., Bonn
ENSINGER, Walter	Dipl.-Ing., Munich
FLICK, Karl-Heinz	Dipl.-Ing. Bau-Ass., Frechen
GORDZIEL, Wolfgang	Dipl.-Ing., Cologne
HACKETHAL, Jan	Dipl.-Ing., Berlin
HENTRICH, Michael	Dipl.-Ing., Berlin
HERBORN, Stephan	Dipl.-Ing. (FH), Frankfurt a. M.
KÖRKEMEYER, Karsten	Dr.-Ing., Cologne
MAIDL, Ulrich	Dr.-Ing., Bochum
NIEDER, Gregor	Dr.-Ing., Alsdorf
RÖMER-SCHMIDT, Albert	Dipl.-Ing., Marsberg
SCHLENTHER, Nico	Dipl.-Ing. (FH), Salzgitter
SOMMERHAGE, Heinrich	Dipl.-Ing., Essen
SUHM, Werner	Dipl.-Ing., Schwanau
UEKER, Klaus Jürgen	Dipl.-Ing., Cologne (deputy spokesperson)
UFFMANN, Hans-Peter	Dr.-Ing., Aachen (spokesperson)
VALTWIES, Erich	Dipl.-Ing., Muenster
VOGLER, Georg	Dr.-Ing., Elsendorf-Mittersetten
VOLK, Hermann	Dipl.-Ing., Spay

Contribution as guest by:

HOCH, Albert	BD Dr.-Ing., Nuernberg
--------------	------------------------

Project organiser within the DWA Head Office:

BERGER, Christian	Dipl.-Ing., Hennef Department Wastewater and Water Protection
-------------------	--

Terms of Clause 3 in alphabetical order

For the purposes of this European Standard the following definitions apply:

3.1 Cutting Head

Tool or system of tools on a common support, which excavates at the face of a bore. The term usually applies to mechanical methods of excavation.

3.2 Expander

A tool which enlarges a bore by displacement of the surrounding ground rather than by excavation.

Abrasiveness

Property of rock causing wear on the drilling tools during drilling.

Blowouts

Release of compressed air or supporting fluid at the ground surface or into a body of water with a large or complete loss of pressure.

CAI

CERCHAR Abrasiveness Index: Rock abrasiveness determined through laboratory tests according to: The Cerchar Abrasivity Index – Plan; Centre d'Etudes et Recherches de Charbonnages de France; Verneuil, 1986.

Construction Prohibition Strip

Protected zone in which the construction of buildings is prohibited. Furthermore, constructions that are to be connected directly or indirectly to national trunk roads via approaches or accesses are subject to the extension prohibition (see Bundesfernstraßengesetz [Federal German Trunk Road Law])

External Diameter

Mean external diameter of the pipe barrel at any cross-section (see DIN EN 14457 and DIN EN 476).

Gradient

The degree of slope of the longitudinal vertical profile (see DIN 18709-2).

Gravity pipeline

Pipeline where flow is caused by the force of gravity and where the pipeline is designed normally to operate partially full.

Internal Diameter

Mean internal diameter of the pipe barrel at any cross section (see DIN EN 14457).

Joint Closure

Constructive measure taken to prevent dirt and foreign substances from entering the joint; no sealing function.

Layout of the Line

Definition of a line in the form of a sequence of line elements (e.g. straight, circle, clothoid, gradient) (see DIN 18709-2).

Line

Horizontal alignment of tunnel or pipejack. (see DIN 18709-2)

Manned technique

Technique involving the use of personnel working in the excavated bore during installation.

Liquefaction

Liquefaction of the soil; complete loss of shear strength as a consequence of dynamic loading.

Overbreak

The extent by which the excavated void including accidental ground losses initially exceeds the outside dimension of the pipe.

Overtcut

The annular space around the pipe deliberately created by using a cutting head or shield of greater dimension than the outside dimension of the pipe.

Overtcut

Half of the difference of borehole diameter and external pipe diameter (ideally, an even annular space around the pipeline).

Pipe jacking

A system of directly installing pipes behind a cutting head and/or shield, by hydraulic jacking from a drive shaft, such that the pipes form a string in the ground.

Pipe Length

Length of the internal pipe barrel (see DIN EN 14457).

Reamer

A cutting head attached to the end of a drill string or pilot rod to enlarge the pilot diameter during a pull-back or pushing operation, to enable a pipe or pipes to be installed.

Relevant Authority

Organisation with appropriate statutory powers of control (see DIN EN 752).

Renovation

Work incorporating all or part of the original fabric of the pipeline by means of which its current performance is improved (EN 752-5: 1997).

Replacement

Construction of a new drain or sewer, on or off the line of an existing drain or sewer, the function of the new drain or sewer incorporating that of the old (EN 752-5: 1997).

RQD-Index

Rock Quality Designation: Property used to describe rock; designates given rock quality based on the length of the drilling cores recovered (in accordance with ASTM D6032-02).

Shield Cradle

Bearing construction in the starting pit to support the machine and pipes.

Spoil

Material excavated and removed in the course of installation.

Sticking Potential

Tendency of clayey soils to stick or adhere, e.g. to the excavation tools of jacking stations.

Subsoil

Soil and/or rock including all substances (e.g. groundwater and contaminations), which serves as a foundation or bedding for structures or which is otherwise affected by construction work (see DIN 4020).

Trenchless construction technique

Any technique for constructing pipelines in the ground without opening trenches.

Pressure Transfer Ring

Component to transfer longitudinal forces between the end faces of the jacking pipes during installation.

Pressure Distribution Ring

Component used to distribute and evenly transfer the forces of the jacking cylinders to the end face of the jacking pipes.

Unmanned technique

Technique avoiding the use of personnel working in the excavated bore during installation.

Weathering Level

Present condition of a rock and/or rock mass as a consequence of the weathering process (in accordance with FGSV 543).

Work Face

Location of where the subsoil is excavated in pipe jacking.

Contents

Introduction to the Joint Publication	3
National Foreword (DIN EN 12889)	3
Introduction	4
Foreword	4
Authors	5
Terms of Clause 3 in alphabetical order	6
3.1 Cutting Head.....	6
3.2 Expander.....	6
List of Figures	15
List of Tables	16
User Notes	17
1 Scope.....	17
2 Normative References.....	18
3 Definitions and Abbreviated Terms	22
3.1 Cutting Head.....	22
3.2 Expander.....	22
3.3 Gravity Pipeline	22
3.4 Overbreak	22
3.5 Overcut	22
3.6 Pipe Jacking	22
3.7 Reamer	22
3.8 Renovation.....	22
3.9 Replacement	22
3.10 Spoil	22
3.11 Trenchless Construction Technique.....	22
3.12 Manned Technique	22
3.13 Unmanned Technique	22
3.1 Definitions	23
3.1.1 Abrasiveness	23
3.1.2 Construction Prohibition Strip.....	23
3.1.3 Blowouts.....	23
3.1.4 External Diameter	23
3.1.5 Pipe Length.....	23
3.1.6 CAI.....	23
3.1.7 Pressure Transfer Ring	23
3.1.8 Pressure Distribution Ring.....	23
3.1.9 Joint Closure	23
3.1.10 Gradient.....	23
3.1.11 Subsoil	23
3.1.12 Internal Diameter.....	23

3.1.13	Liquefaction	23
3.1.14	Work Face.....	23
3.1.15	RQD-Index	23
3.1.16	Shield Cradle	24
3.1.17	Line.....	24
3.1.18	Layout of the Line	24
3.1.19	Overcut	24
3.1.20	Sticking Potential	24
3.1.21	Weathering Level	24
3.1.22	Relevant Authority	24
3.2	Abbreviated Terms.....	24
4	General	25
5	Construction Components and Materials/Jacking Pipes, Pipe Joints and Shafts.....	25
5.1	General	25
5.2	Pipes and Joints	25
5.3	Manholes and Inspection Chambers.....	25
5.4	Delivery, Handling and Transportation on Site	25
5.5	Storage	26
5.2	Jacking Pipes.....	26
5.2.1	Materials.....	26
5.2.2	Information by the Manufacturer	27
5.2.3	General Dimensions and Tolerances	27
5.2.3.1	Pipe Length Tolerances	27
5.2.3.2	Squareness of the End Faces	27
5.2.3.3	Deviation from the Straight Line	27
5.2.3.4	External Diameter	27
5.2.3.5	Steps or Lips in Invert	29
5.3	Pipe Joints.....	29
5.3.1	Components	29
5.3.1.1	Socket and Spigot Joints	29
5.3.1.2	Welded Joints for Steel Pipes	29
5.3.2	Information Provided by the Manufacturer	29
5.3.3	Tightness of the Pipe Joints.....	29
5.3.3.1	General	29
5.3.3.2	Angular Deflection	30
5.3.3.3	Transverse Force Stability	30
5.3.4	Transfer of Longitudinal Forces.....	30
5.3.5	Transfer of Transverse Forces.....	31
5.3.6	Design of the Pipe Joints	31
5.3.7	Material of the Collars or Guide Rings	33
5.3.8	Material of the Seals	33
5.3.9	Delivery Condition	33
5.4	Special Construction Components	33
5.4.1	Transport Anchor	33
5.4.2	Rolling Protection	33

5.4.3	Injection Holes or Ports	34
5.4.4	Intermediate Jacking Stations (Interjacks)	34
5.4.5	Pressure Distribution Ring of the Main Jacking Station	35
5.5	Packaging	35
5.6	Connections	35
5.7	Manholes	35
5.8	Quality Control	35
5.9	Labelling	35
6	Techniques	36
6.0	Classification	36
6.1	Unmanned Techniques	36
6.1.1	General	36
6.1.2	Non-steerable Processes	36
6.1.2.0	Areas of Application	38
6.1.2.1	Soil Displacement Techniques	38
6.1.2.1.0	General	38
6.1.2.1.1	Impact Moling/Soil Displacement Hammer	39
6.1.2.1.2	Pipe Ramming/Pushing with Closed Pipe	39
6.1.2.1.3	Rod pushing with an expander/Horizontal Jacking Plant with Expander	40
6.1.2.1.4	Pipe Bursting	41
6.1.2.1.5	Pipe Extraction/Pipe Renewal	42
6.1.2.2	Soil Removal Techniques	44
6.1.2.2.1	Pipe Ramming/Pushing with an Open Ended Pipe	44
6.1.2.2.2	Auger Boring	45
6.1.2.2.3	Hammer Drilling	46
6.1.2.2.3	Overdrilling	46
6.1.2.2.4	Rod Pushing with a Reamer	47
6.1.3	Steerable Techniques	47
6.1.3.1	Microtunnelling	47
6.1.3.1.1	General	47
6.1.3.1.2	Microtunnelling with Auger Spoil Removal	47
6.1.3.1.3	Slurry Shield Microtunnelling	49
6.1.3.1.4	Microtunnelling Spoil Removal by Vacuum	50
6.1.3.1.4	Slurry Shield Microtunnelling with Compressed Air Cushion (Mixshield)	50
6.1.3.1.5	Microtunnelling Spoil Removal by other mechanical Means	50
6.1.3.1.5	Microtunnelling with Muck Conveyance and Earth Pressure Balance (EPB shield)	50
6.1.3.1.6	Microtunnelling Incorporating Pipe Eating	50
6.1.3.1.6	Microtunnelling with Other Removal Techniques	50
6.1.3.1.7	Pipe-eating	50
6.1.3.2	Pilot jacking with Pipe Bore Pilot Pipe Jacking	51
6.1.3.2.1	General	51
6.1.3.2.2	Pilot Pipe Jacking with Soil Displacement	52
6.1.3.2.3	Pilot Pipe Jacking with Soil Removal	52
6.1.3.3	Directional Drilling HDD (Horizontal Directional Drilling)	53

6.2	Manned Techniques	54
6.2.1	Pipe Jacking General	54
6.2.2	Other Manned Techniques	54
6.2.2	Non-steerable Techniques	54
6.2.3	Steerable Techniques	54
6.2.3.1	General	54
6.2.3.2	Shield (open) with Partial Face Excavation without Support or with Mechanical Partial Support	55
6.2.3.3	Shield (open) with Partial Face Excavation without Support or with Mechanical Partial Support by Compressed Air Pressurisation of the Working Face	55
6.2.3.4	Shield (open) with Full Face Excavation with Mechanical Partial Support without or by Compressed Air Pressurisation of the Working Face	56
6.2.3.5	Shield (closed) with Full Face Excavation and Fluid Support and Compressed Air (Mixshield)	56
6.2.3.6	Shield (closed) with Full Face Excavation and Earth Pressure Balance (EPB shield)	57
7	Requirements of Planning and Construction	58
7.0	General	58
7.1	Protection of Existing Structures	58
7.1	Basic Evaluation, Design and Construction Planning, Call for Tender and Award	58
7.1.1	General	58
7.1.2	Survey of Existing Structures and Systems	58
7.1.3	Subsoil and Groundwater	58
7.1.4	Minimum Clear Dimensions	60
7.1.5	Subsidence, Heaves, Cover	61
7.1.6	Layout of the Line	62
7.1.7	Tolerances	62
7.1.8	Starting, Intermediate and Target Pits	62
7.1.9	Working Face Support	63
7.1.10	Additional Measures in Water Bearing Subsoil	63
7.1.11	Obstacles	64
7.1.12	Soil Conditioning	64
7.1.13	Structural Calculation	64
7.1.14	Construction Site Arrangement	64
7.1.15	Call for Tenders and Placing	64
7.2	Special Requirements, Work Preparation and Construction	65
7.2.1	General	65
7.2.2	Starting, Intermediate and Target Pits	65
7.2.3	Exit and Entry Processes	66
7.2.4	Structural Calculation of Jacking Pipes and Construction Pits	66
7.2.5	Overtcut	67
7.2.6	Recording and Logging of Jacking Parameters	67
7.2.7	Support of the Working Face	68
7.2.7.1	Water Control Using Compressed Air	68
7.2.8	Lubricant and Supporting Medium	68
7.3	Safeguarding Design Assumptions	69
7.4	Information about Ground Conditions	69
7.5	Data Collection during Installation	69
7.6	Stability during Construction	70

7.6.1	Launch and Reception Shafts	70
7.6.2	Pipeline.....	70
7.6.3	Guidance System.....	70
7.7	Overtcut	70
7.8	Overbreak	70
7.9	Settlement and Heave.....	70
7.10	Deviation in Line and Level.....	70
8	Inspection and Testing of Pipelines after Installation	70
8.1	Visual Inspection.....	70
8.2	Leaktightness	70
9	Procedures and Requirements for testing Gravity Pipelines	71
9.1	General	71
9.2	Testing with Air (method "L")	71
9.3	Testing with Water (method "W")	74
9.3.1	Test Pressure.....	74
9.3.2	Conditioning Time	74
9.3.3	Testing Time	74
9.3.4	Test Requirements	74
9.4	Testing of Each Individual Joint.....	74
10	Testing of Pressure Pipelines.....	75
11	Qualifications	75
8	Pipe Jacking and Related Techniques under Federal Railway Property	75
8.1	General	75
8.2	Construction-type-specific Regulations.....	76
8.3	Additional Requirement of Slab Tracks	76
8.4	Protective Measures	77
8.4.1	General	77
8.4.2	Operational Protective Measures.....	77
8.4.3	Constructional Protective Measures	77
8.5	Limiting Values for Track Bed Changes	78
8.6	Application Conditions for Jacking Techniques	78
8.6.1	Unmanned, Non-steerable Techniques	78
8.6.1.1	Soil Displacement Techniques	78
8.6.1.2	Soil Removal Techniques	78
8.6.1.2.1	Horizontal Ramming/Jacking with Open Pipe	78
8.6.1.2.2	Auger Boring.....	78
8.6.1.2.3	Overdrilling.....	78
8.6.2	Steerable Techniques	78
8.6.2.1	Microtunnelling	78
8.6.2.2	Pilot Pipe Jacking	78
8.6.2.3	HDD	79
8.6.3	Manned Techniques	79
8.6.4	Other Installation Techniques	79
8.7	Documentation	79

9	Pipe Jacking and Related Techniques under Federal German Trunk Roads	79
9.1	General	79
9.2	Preparatory Measures	80
9.3	Operational Protective Measures.....	80
9.4	Constructional Protective Measures	81
9.5	Operating Conditions for Jacking Techniques	81
9.6	Documentation	81
10	Pipe Jacking and Related Techniques under Federal German Waterways	82
10.1	General	82
10.2	Authorisation/Approval	82
10.3	Constructional and Operational Protective Measures	83
10.3.1	Facilities by the Federal Waterways and Shipping Administration	83
10.3.2	Third Party Systems	83
10.3.3	Subsoil	83
10.3.4	Sealing Paths of Federal Waterways.....	83
10.3.5	Other Federal Waterways.....	84
10.3.6	Starting and Target Pits	84
10.3.7	Interruption of Work.....	84
10.3.8	Obstacles.....	84
10.3.9	Accidents or Emergencies.....	84
10.3.10	Safety of Shipping Traffic.....	85
10.4	Application Conditions of Jacking Techniques	85
10.4.1	HDD	85
10.4.2	Monitoring	85
10.4.3	Working Logs	85
10.5	As-Built Documents	86
11	Economic Aspects in Pipe Jacking of Drains and Sewers.....	86
12	Regulations and Other Rules.....	87
Laws/Directives.....	87	
Accident Prevention Regulations	87	
Safety Regulations	87	
Standards	87	
Other Regulations/Rules	88	
Sources of Supply.....	88	
Annex A	(informative) Abstract from Council Directive of 17 September 1990 on the Procurement Procedures of Entities operating in the Water, Energy, Transport and Telecommunication Sectors	89
Footnotes on the Material Table (Annex A)	Fehler! Textmarke nicht definiert	

List of Figures

Figure 1:	Squareness of the end faces	27
Figure 1:	Trenchless techniques.....	36
Figure 2:	Angular deflection α of the pipe joint.....	30
Figure 2:	Example of impact moling	38
Figure 3:	Sketch of a pipe joint with single-sided fixed guide ring for jacking pipes made of concrete, steel fibre concrete and reinforced concrete	32
Figure 3:	Example of pipe ramming with a pipe closed at its leading end	38
Figure 4:	Sketch of a pipe joint with loose guide ring and sealing elements.....	32
Figure 4:	Example of rod pushing with an expander.....	39
Figure 5:	Sketch of a pipe joint with one-sided fixed guide ring and integrated sealing element	33
Figure 5:	Example of pipe bursting	40
Figure 6:	Pipe jacking and related techniques.....	38
Figure 6:	Example of pipe extraction	41
Figure 7:	Example horizontal ram/jacking plant with open pipe.....	44
Figure 7:	Example of pipe ramming/pushing with an open ended pipe	43
Figure 8:	Example auger boring.....	45
Figure 9:	Example overdrilling.....	46
Figure 9:	Example of hammer drilling	45
Figure 10:	Example microtunnelling with auger spoil removal	48
Figure 11:	Example slurry shield microtunnelling.....	49
Figure 12:	Example microtunnelling with muck conveyance with optional re-treatment of the soil.....	50
Figure 12:	Example of pilot jacking with pipe bore	50
Figure 13:	Example pilot pipe jacking with soil displacement	52
Figure 13:	Example of directional drilling.....	51
Figure 14:	Example pilot pipe jacking with soil removal	52
Figure 14:	Flow diagram method "L"	72
Figure 15:	Horizontal Directional Drilling (HDD)	53
Figure 15:	Flow diagram method "W"	72
Figure 16:	Example shield (open) with partial face excavation with partial support.....	55
Figure 17:	Example shield (open) with partial face excavation without support by compressed air pressurisation of the working face	55
Figure 18:	Example shield (open) with full-face excavation with mechanical partial support without compressed air pressurisation of the working face.....	56
Figure 19:	Shield (closed) with full-face excavation and fluid-support and compressed air (Mixshield)	56
Figure 20:	Shield (closed) with full-face excavation and earth pressure balance (EPB-shield)	57
Figure 21:	Constant employment of personnel with manned techniques in atmospheric conditions	60

List of Tables

Table 1:	Pipe length tolerances in [mm]	27
Table 1:	Test pressure, pressure drop and testing times for testing with air.....	73
Table 2:	Permissible deviation from squareness in [mm]	28
Table 3:	Permissible deviation from the straight line in [mm]	28
Table 4:	Permissible deviation from the maximum external pipe diameter in [mm]	28
Table 5:	Deflection in [mm] per [m] pipe length.....	30
Table 6:	Internal seals for jacking pipes	34
Table 7:	Overview of the unmanned non-steerable techniques listed.....	43
Table 8:	Description of the subsoil and groundwater conditions	59
Table 9:	Temporary employment of personnel with the unmanned technique.....	61
Table 10:	Maximum deviation in [mm] from the target position for drains and sewers.....	62
Table 11:	Examples of construction pit sizes.....	63

PREVIEW

User Notes

This Standard is the result of honorary, technical-scientific/economic collaboration which has been achieved in accordance with the principles applicable therefore (statutes, rules of procedure of the DWA and Standard DWA-A 400). For this, according to precedents, there exists an actual presumption that it is textually and technically correct and also generally recognised.

Application of this Standard is open to everyone. However, an obligation for its application can arise from legal or administrative regulations, a contract or other legal reasons.

This Standard is an important, however not the only source of information for correct solutions. With its application no one avoids responsibility for his own actions or for its correct application in specific cases; this applies in particular for correct use of margins described in this Standard.

1 Scope

This European Standard is applicable to the trenchless construction and testing of new drains and new sewers in the ground, which are normally operating as gravity pipelines, formed using prefabricated pipes and their joints. The trenchless construction and testing of drains and sewers operating under pressure is also covered by this European Standard together with prEN 805:1999 as appropriate.

This European Standard also applies to trenchless replacement techniques. Renovation techniques for existing sewers and drains are not covered by this European Standard.

Methods of trenchless construction include

- manned and unmanned techniques;
- steerable and non-steerable techniques.

NOTE 1: Mining or tunnelling (e.g. in situ construction or the use of prefabricated segments) are not covered by this European Standard although some parts may apply to these methods. Additional requirements apply for mining and tunnelling methods for the construction of drains and sewers.

Additionally other local or national regulations should be taken into account, e.g. concerning health and safety, pavement installation, tolerances for deviation in line and level and requirements for leaktightness testing.

NOTE 2: Requirements for associated pipeline installation work other than trenchless construction, e.g. for manholes and inspection chambers, are given in EN 1610 "Construction and testing of drains and sewers".

This Standard deals with the underground installation of pre-fabricated pipes with different geometry of the cross-section. During the installation, a cavity is created in the ground by displacing, ramming, drilling, pressing or other excavation. The pipes are pulled, pushed or jacked into this cavity or into existing sewers or pipelines are relined and/or replaced.

For shield drives (e.g. segment lining, shotcrete), which are not described in the Standard, the Standard can be applied correspondingly. However, it does not apply to mining techniques.

This Standard does not apply to processes related to pipe jacking if the respective requirements are summarised in individual DVGW and/or DWA Standards or Advisory Leaflets. This exception does not apply to railway property, Federal German trunk roads or waterways.

If techniques related to pipe jacking are used for purposes other than public gas, water supply and/or wastewater disposal, it is recommended to apply the respective Standards and Advisory Leaflets as well.

Clause 9 only applies to drains and sewers. If water or gas pipelines are built under federal trunk roads, the technical regulations contained or specified in the licence agreement are applied.

PREVIEW



ISBN 978-3-942964-37-1 (Print)
978-3-96862-096-1 (E-Book)

German Association for Water, Wastewater and Waste
Deutsche Vereinigung für Wasserwirtschaft, Abwasser und Abfall e. V.
Theodor-Heuss-Allee 17 · 53773 Hennef · Germany
Tel.: +49 2242 872-333 · Fax: +49 2242 872-100
E-Mail: info@dwa.de · Internet: www.dwa.de